

**New Traffic Signal Installation No. Mountain Ave & Watchung Ave
Township of Montclair, Essex County, NJ
Bid Opening Date: February 07, 2007**

SUMMARY OF BIDS

				Foggia Contracting Co. 262 Timber Drive Berkeley Hts,NJ 07922 908-413-5588		Zuccaro & Sons Inc. 64 Commerce Street Garfield, NJ 07026 973-472-9554		Orchard Holdings, LLC 200 South Ave Suite 5 Middlesex, NJ 08846 732-560-8200		Fai-Gon Electric Inc. 140 11th Street Piscataway, NJ 08854 732-968-9400	
ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
1	Earth Excavation For Test Pits	5	CY	50.00	250.00	10.00	50.00	73.15	365.75	50.00	250.00
2	Construction Signs	300	SF	5.00	1,500.00	10.00	3,000.00	1.00	300.00	13.45	4,035.00
3	Breakaway Barricades	15	UN	50.00	750.00	25.00	375.00	1.00	15.00	10.00	150.00
4	Drums	25	UN	10.00	250.00	25.00	625.00	1.00	25.00	75.00	1,875.00
5	Traffic Cones	75	UN	3.00	225.00	10.00	750.00	1.00	75.00	5.00	375.00
6	Construction Identification Signs 8' x 4'	2	UN	750.00	1,500.00	750.00	1,500.00	700.00	1,400.00	1,500.00	3,000.00
7	Traffic Directors, Police Officer	100	HR	47.00	4,700.00	47.00	4,700.00	47.00	4,700.00	47.00	4,700.00
8	Traffic Stripes	1,000	LF	2.00	2,000.00	2.00	2,000.00	0.70	700.00	1.00	1,000.00
9	Traffic Markings, Lines, Long Life, Thermoplastic	1,520	LF	3.00	4,560.00	3.00	4,560.00	1.30	1,976.00	1.00	1,520.00
10	Overhead Street Name Sign, Type DF	25	SF	80.00	2,000.00	75.00	1,875.00	61.35	1,533.75	88.00	2,200.00
11	Signs	25	SF	45.00	1,125.00	50.00	1,250.00	52.80	1,320.00	35.20	880.00
12	2" Rigid Metallic Conduit, Type CUG	45	LF	25.00	1,125.00	25.00	1,125.00	28.20	1,269.00	20.00	900.00
13	3" Rigid Nonmetallic Conduit, Type CUG	60	LF	30.00	1,800.00	35.00	2,100.00	25.20	1,512.00	39.00	2,340.00
14	3" Rigid Nonmetallic Conduit, Type CUR	240	LF	40.00	9,600.00	60.00	14,400.00	65.60	15,744.00	46.00	11,040.00
15	Ground Wire, No. 8 AWG	360	LF	2.50	900.00	2.00	720.00	2.45	882.00	2.65	954.00
16	Service Wire, No. 6 AWG	190	LF	4.00	760.00	5.00	950.00	2.85	541.50	3.75	712.50
17	Foundations, Type ECS-STD (8" STD)	2	UN	2,800.00	5,600.00	1,500.00	3,000.00	6,305.00	12,610.00	2,950.00	5,900.00
18	Foundations, Type ECS-STD (10" STD)	2	UN	3,100.00	6,200.00	1,700.00	3,400.00	6,455.00	12,910.00	3,050.00	6,100.00
19	Foundations, Type Mc	1	UN	2,000.00	2,000.00	2,400.00	2,400.00	2,210.00	2,210.00	2,050.00	2,050.00
20	18" x 36" Junction Boxes	4	UN	1,600.00	6,400.00	2,000.00	8,000.00	1,370.00	5,480.00	1,800.00	7,200.00
21	Controller Assemblies, 12 Phase	1	UN	11,000.00	11,000.00	32,000.00	32,000.00	30,230.00	30,230.00	32,800.00	32,800.00
22	Video Interface Cable	200	LF	5.00	1,000.00	4.00	800.00	4.50	900.00	4.50	900.00
23	Video Detection Unit	2	UN	5,500.00	11,000.00	7,500.00	15,000.00	10,180.00	20,360.00	6,666.00	13,332.00
24	Meter Cabinets, Type T	1	UN	2,500.00	2,500.00	1,900.00	1,900.00	1,290.00	1,290.00	1,880.00	1,880.00
25	Pedestrian Signal Assemblies, Type W-1-CT	10	UN	900.00	9,000.00	1,200.00	12,000.00	1,295.00	12,950.00	1,055.00	10,550.00
26	Push Button Assemblies, w/R10-3e	4	UN	150.00	600.00	350.00	1,400.00	235.00	940.00	240.00	960.00
27	Traffic Signal Assemblies, Type ECS 15MA-2	2	UN	4,000.00	8,000.00	4,500.00	9,000.00	4,110.00	8,220.00	3,455.00	6,910.00
28	Traffic Signal Assemblies, Type ECS 20MA-2	1	UN	4,200.00	4,200.00	4,200.00	4,200.00	4,285.00	4,285.00	3,680.00	3,680.00
29	Traffic Signal Assemblies, Type ECS 25MA-2	1	UN	4,500.00	4,500.00	4,500.00	4,500.00	4,440.00	4,440.00	3,900.00	3,900.00
30	Traffic Signal Cable--2 Conductor	530	LF	1.50	795.00	2.50	1,325.00	2.25	1,192.50	2.55	1,351.50
31	Traffic Signal Cable--5 Conductor	1,550	LF	3.50	5,425.00	3.00	4,650.00	2.75	4,262.50	2.95	4,572.50
32	Traffic Signal Cable--10 Conductor	525	LF	4.25	2,231.25	3.50	1,837.50	3.50	1,837.50	3.50	1,837.50
33	Traffic Signal Standards, Type ECS-6x8	2	UN	2,700.00	5,400.00	3,400.00	6,800.00	3,400.00	6,800.00	3,365.00	6,730.00
34	Traffic Signal Standards, Type ECS-8x10	2	UN	3,000.00	6,000.00	3,600.00	7,200.00	3,650.00	7,300.00	3,730.00	7,460.00
35	Traffic Controller Assembly Turn-On	1	UN	1,800.00	1,800.00	3,000.00	3,000.00	1,050.00	1,050.00	5,800.00	5,800.00
36	Trimming Existing Trees, Over 12" to 18" Diameter	5	UN	100.00	500.00	600.00	3,000.00	270.00	1,350.00	200.00	1,000.00
37	Concrete or Granite Block Curb	700	LF	20.00	14,000.00	35.00	24,500.00	56.00	39,200.00	68.00	47,600.00
38	Concrete Sidewalk, 7" Thick	600	SY	63.00	37,800.00	75.00	45,000.00	68.80	41,280.00	105.00	63,000.00
39	Milling, +/-2" Thick	3,300	SY	14.50	47,850.00	17.00	56,100.00	14.20	46,860.00	11.00	36,300.00
40	Hot Mix Asphalt Surface Course	600	TON	123.50	74,100.00	119.00	71,400.00	133.20	79,920.00	120.00	72,000.00
41	DuraTherm Traffic Marking or approved equal	6,200	SF	14.50	89,900.00	16.00	99,200.00	14.05	87,110.00	15.00	93,000.00
42	Detectable Warning Surface	30	SY	305.00	9,150.00	150.00	4,500.00	258.80	7,764.00	281.00	8,430.00
	TOTAL				\$399,996.25		\$466,092.50		\$475,110.50		\$481,175.00